


(1)

कार्यालय
भोपाल सहकारी दुग्ध संघ मर्यादित, भोपाल

निविदा फार्म

संघ की पुताई, वॉटर प्रूफिंग का कार्य, पेवर बलॉक लगाने का कार्य, नवीन जेंट्स एवं लेडीज टॉयलेट निर्माण का कार्य, प्रशासन भवन एवं मार्केटिंग भवन के टॉयलेट रिनोवेशन का कार्य एवं कैंटीन रिनोवेशन के कार्यों के संपादन हेतु।

ई-निविदा द्वितीय



(निविदा फार्म का मूल्य ₹0 2000/-)

(निविदा फार्म क्र ———)

कार्यालय — डेयरी प्लांट, हबीबगंज, भोपाल-462024 (म0 प्र0)
0755-2478250-51,52,53 - फेक्स, 0755.2450896

क्रं.	विवरण ।	पृष्ठ क्रमांक
1	आवरण पृष्ठ	01
2	अनुक्रमणिका	02
3	ई-निविदा सूचना विज्ञप्ति	03
4	अनुसूची प्रथम –निविदा कार्यक्रम एवं सामान्य निर्देश	04
5	अनुसूची द्वितीय –तकनीकी निविदा प्रपत्र –1	05
6	अनुसूची तृतीय –नियम शर्तें एवं वित्तीय निविदा प्रपत्र – 2 (निविदा दर प्रस्ताव पत्रक सहित)	06 से 11
7	शेड्यूल आफ आईटम्स	12 से 27
8	एम.पी.पी.डबल्यू.डी. का आदेश ।	28
कुल पृष्ठ – 28.		

भोपाल सहकारी दुग्ध संघ मर्यादित, भोपाल।

डेयरी प्लांट, हबीबगंज, भोपाल 462024 (म0 प्र0)

फोन नं. 0755 - 2478250- 51,52,53

निविदा सूचना क्र. / भो.स.दु.सं./ यॉ.-सिविल- / 2025

दिनांक.

संघ की पुताई, वॉटर प्रूफिंग का कार्य, पेवर बलॉक लगाने का कार्य, नवीन जेंट्स एवं लेडीज टॉयलेट निर्माण का कार्य, प्रशासन भवन एवं मार्केटिंग भवन के टॉयलेट रिनोवेशन का कार्य एवं कैंटीन रिनोवेशन के कार्यों आदि के संपादन हेतु। ई- निविदा द्वितीय तदनुसार ई-निविदा द्वितीय दि. 08.09.2025 को दोपहर 3:00 बजे तक ऑन लाईन के माध्यम से मध्य प्रदेश शासन की वेब- साईट www.mptenders.gov.in पर डाउन लोड किया जा सकेगा। जो कि निम्नलिखित अनुसार है।

क्रं.	कार्य का विवरण।	निविदा प्रपत्र का मूल्य।	अमानत राशि (EMD)	कार्य की अनुमानित लागत। (लाखों में)
1	संघ की पुताई, वॉटर प्रूफिंग का कार्य, पेवर बलॉक लगाने का कार्य, नवीन जेंट्स एवं लेडीज टॉयलेट निर्माण का कार्य, प्रशासन भवन एवं मार्केटिंग भवन के टॉयलेट रिनोवेशन का कार्य एवं कैंटीन रिनोवेशन के कार्यों के संपादन हेतु।	रु 2,000 /—	रु 1,36,200 /—	रु. 68.10 लाख

निविदा फार्म का मूल्य एवं अमानत राशि ऑन लाईन पर भुगतान की जाना है। निविदा की वैधता खुलने के बाद 90 दिन तक है। ऑन लाईन के माध्यम से निविदाकार को दिनांक- 08.09.2025 तक दोपहर 3:00 बजे तक भोपाल दुग्ध संघ के प्रशासन विभाग में स्वयं के लोक निर्माण विभाग के पंजीयन का प्रमाण पत्र एवं वांछित कागजात जमा करने हैं। प्राप्त निविदायें ऑन लाईन पर दिनांक- 09.09.2025 को दोपहर 3:00 बजे खोली जावेगी। अन्य विस्तृत जानकारी एम.पी.सी.डी.एफ., की वेब साइट www.sanchibhopal.com से प्राप्त की जा सकती है समस्त अथवा कुछ निविदाओं को अंशतः या पूर्णतः निरस्त करने का अधिकार मुख्य कार्यपालन अधिकारी को होगा।

मुख्य कार्यपालन अधिकारी
भोपाल सहकारी दुग्ध संघ मर्यादित,
भोपाल।

(4)

— अनुसूची प्रथम—
भोपाल सहकारी दुग्ध संघ मर्यादित, भोपाल
(सामान्य निर्देश)

- 1 निविदा सूचना क्रं. का विवरण — ई— निविदा द्वितीय सूचना क्रं.
/भो.स.दु.सं./ यो—सिविल/...../ 2025 दि०
- 2 निविदा फार्म का मूल्य — राशि रु० 2,000/—
भोपाल सहकारी दुग्ध संघ मर्यादित, भोपाल।
- 3 ई—निविदा (द्वितीय) दि. 08.09.2025 दोपहर 3:00 बजे तक ऑन लाईन माध्यम से मध्य प्रदेश शासन की वेब— साईट www.mptenders.gov.in से डाउन लोड एवं जमा किया जायेगा।

संघ की पुताई, वॉटर प्रूफिंग का कार्य, पेवर बलॉक लगाने का कार्य, नवीन जेंट्स एवं लेडीज टॉयलेट निर्माण का कार्य, प्रशासन भवन एवं मार्केटिंग भवन के टॉयलेट रिनोवेशन का कार्य एवं कैंटीन रिनोवेशन के कार्यों के संपादन हेतु।	रु. 1,36,200/—अमानत राशि (EMD)
--	--------------------------------

4. कार्य का विवरण — संघ की पुताई, वॉटर प्रूफिंग का कार्य, पेवर बलॉक लगाने का कार्य, नवीन जेंट्स एवं लेडीज टॉयलेट निर्माण का कार्य, प्रशासन भवन एवं मार्केटिंग भवन के टॉयलेट रिनोवेशन का कार्य एवं कैंटीन रिनोवेशन के कार्यों के संपादन हेतु। कार्य की निविदा दरें ऑन लाईन निर्धारित प्रोफार्मा में भरनी हैं। निविदा दरें भरने से पूर्व निविदाकार को अनुसूची (तृतीय) के बिन्दु क्र० 10 एवं 9—21 का अध्ययन किया जाना अनिवार्य है।
5. कार्य का मूल्य — रु. 68.10 लाख।
6. ऑन लाईन माध्यम से निविदाकार को दिनांक— 08.09.2025 दोपहर 3:00 बजे तक अपना पंजीयन एवं वांछित कागजात जमा करने हैं।
7. प्राप्त निविदायें दिनांक 09.09.2025 दोपहर 3:00 बजे खोली जावेगी।
8. अन्य विस्तृत जानकारी एम.पी.सी.डी.एफ., की वेब साइट www.sanchibhopal.com से प्राप्त की जा सकती है।
9. समस्त अथवा कुछ निविदाओं को अंशतः या पूर्णतः निरस्त करने का अधिकार मुख्य कार्यपालन अधिकारी को होगा।
10. सिविल कार्यों हेतु दरें एम.पी.पी.डबल्यू.डी., के 01 जनवरी सन् 2024 से लागू एस.ओ.आर., के अनुसार ऑन लाईन प्रोफार्मा पर भरनी हैं।

(5)

अनुसूची द्वितीय
भोपाल सहकारी दुग्ध संघ मर्याद भोपाल
डेयरी प्लांट हबीबगंज, भोपाल।

प्रति,

मुख्य कार्यपालन अधिकारी
भोपाल सहकारी दुग्ध संघ मर्याद भोपाल।

विषय:- संघ की पुताई, वॉटर प्रूफिंग का कार्य, पेवर बलॉक लगाने का कार्य, नवीन जेंट्स एवं लेडीज टॉयलेट निर्माण का कार्य, प्रशासन भवन एवं मार्केटिंग भवन के टॉयलेट रिनोवेशन का कार्य एवं कैंटीन रिनोवेशन के कार्यों के संपादन हेतु।

- (1) निविदाकार का नाम :- _____
(2) पूरा पता :- _____
(3) फोन नं०/मोबाइल नं० :- _____
(4) लो०नि०विभाग म०प्र० में पंजीयन व श्रेणी का विवरण :- _____

5. PAN का विवरण :- _____

06. निविदाकार के जी.एस.टी. नंबर का विवरण :- _____

07. निर्माण कार्य अनुभव संबंधी विवरण :-

क्र.	निर्माण कार्य का विवरण			कार्य आदेश जारीकर्ता विभाग का विवरण	
	कार्य का विवरण	लागत राशि	कार्य पूर्ण करने की दिनांक	विभाग का नाम	कार्यादेश क्र. /दिनांक.
1					
2					

(उपरोक्त विवरण के साथ ही सिविल कार्य के आदेश एवं चाहे गये प्रमाण पत्र ऑन लाईन से जमा करने हैं।

निविदा प्रपत्र में वर्णित दुग्ध संघ के समस्त नियम व शर्तें मुझे पूर्णतः मान्य हैं, व मेरे द्वारा प्रस्तावित कार्य व स्थल का निरीक्षण कर लिया गया है। उपरोक्तानुसार प्रदाय की गई जानकारी पूर्णतः सत्य है। यदि प्रस्तुत जानकारी असत्य पाई जाती है तो मेरी निविदा निरस्त की जा सकती है, जिसके लिये मैं स्वयं जवाबदार रहूंगा।

स्थान _____

दिनांक _____

हस्ताक्षर निविदाकार

नाम _____

अनुसूची तृतीय
(नियम व शर्तें आदि)

निर्देशानुसार संघ की पुताई, वॉटर प्रूफिंग का कार्य, पेवर बलॉक लगाने का कार्य, नर्वीन जेंटस एवं लेडीज टॉयलेट निर्माण का कार्य, प्रशासन भवन एवं मार्केटिंग भवन के टॉयलेट रिनोवेशन का कार्य एवं कैंटीन रिनोवेशन के कार्यों के संपादन हेतु ऐस्टीमेट तैयार किया गया। जिसका ऐस्टीमेट निम्नानुसार है। पृष्ठ 12 से 27 पर दिये गये विवरण अनुसार कार्य किया जाना है। लोक निर्माण विभाग में पंजीकृत ठेकेदार ऑन लाईन निविदा जमा कर सकते हैं।

- 1 प्रस्तावित कार्य हेतु निर्धारित अमानत राशि रु0 1,36,200/- बगैर प्राप्त निविदा अमान्य मानी जावेगी। अमानत राशि पर किसी प्रकार का ब्याज देय नहीं होगा। सफल निविदाकारों की अमानत राशि, आवंटित कार्य पूर्ण होने की दिनांक से 24 माह पश्चात् वापस की जावेगी।
- 2 सफल निविदाकार को राशि रु. 1,00,000/- कि बैंक ग्यारंटी जमा करनी पड़ेगी। जो कार्य पूर्ण होने के 01 मानसून के पश्चात् कार्य की स्थिति देखते हुये वापिस की जावेगी। इसके बिना कार्यादेश दिया नहीं जायेगा।
- 3 सफल निविदाकार के प्रत्येक बिल में से 5 प्रतिशत सुरक्षा राशि का कटौत किया जायेगा।
- 4 निविदाकार यदि एम.पी.पी.डबल्यू.डी. एस.ओ.आर से 10 प्रतिशत कम रेट भरते हैं तो सफल निविदाकार को निविदा की कुल राशि का उतना प्रतिशत डी.डी. के रूप में दुग्ध संघ में जमा करना पड़ेगा और कार्य न करने की स्थिति में उनकी यह राशि अमानत राशि के साथ जब्त कर ली जावेगी। जैसे यदि वह 10 प्रतिशत एस.ओ.आर से नीचे रेट भरता है तो कुल निविदा राशि रुपये 100.00 लाख का 3 प्रतिशत रुपये 3,00,000/- जमा करने होंगे। इस स्थिति में भी यदि मुख्य कार्यपालन अधिकारी भरी गई निविदा दर कार्य करने योग्य नहीं पाते हैं तो वे निविदा निरस्त करने का अधिकार रखते हैं।

(5) सुरक्षा निधि:-

- 5-1 कार्य के प्रत्येक चलित देयकों से 5% राशि सुरक्षा निधि के रूप में कटौत की जावेगी। उक्त राशि आवंटित कार्य पूर्णता की दिनांक से 2 वर्ष की अवधि तक दुग्ध संघ में जमा रहेगी तथा कार्य के संतोषजनक पाये जाने पर ही वापिस की जावेगी।
- 5-2 सुरक्षा निधि पर दुग्ध संघ द्वारा किसी भी तरह का ब्याज देय नहीं होगा।

(6) डिफेक्ट लाएबिलिटी अवधि (Defect Liability period)

- 6-1 डिफेक्ट लाएबिलिटी अवधि कार्य पूर्णता दिनांक से 2 वर्ष की अवधि होगी।
- 6-2 डिफेक्ट लाएबिलिटी अवधि में कार्यों में यदि किसी भी प्रकार का डिफेक्ट पाया जाता है तो सफल निविदाकर्ता को पत्र/दूरभाष पर सूचना दिये जाने की दिनांक से 07 दिवस की अवधि में बताये गये डिफेक्ट/डिफेक्ट्स का स्वयं के व्यय पर सुधार कार्य करना होगा।
- 6-3 निर्धारित समयावधि में बताये गये डिफेक्ट/डिफेक्ट्स का सुधार कार्य पूर्ण न किये जाने की स्थिति में दुग्ध संघ द्वारा किसी अन्य ऐजेन्सी/विभागीय स्तर से बताये गये डिफेक्ट/डिफेक्ट्स का सुधार कार्य कराकर जमा सुरक्षा निधि व अमानत राशि से सुधार कार्य की राशि का समायोजन कर लिया जावेगा।

(7) निर्माण कार्य अवधि -

- 7-1 निर्माण कार्य हेतु निर्माण अवधि कार्य आदेश जारी होने की दिनांक से 15 दिन के भीतर कार्य चालू किया जाना है।

(8) दर —

8-1 निविदा प्रस्तुतकर्ताओं द्वारा प्रस्तुत दर की वैधता निविदा खोलने की दिनांक से 90 दिवस होगी, परन्तु यदि प्रस्तुत दरें अमान्य की जाती हैं तो पुनः निविदा जारी किये जाने की दिनांक से पूर्व दर वैधता स्वमेव समाप्त मानी जावेगी।

8-2 निविदाकर्ताओं द्वारा प्रस्तुत दर स्थिर होना चाहिये, साथ ही दुग्ध संघ द्वारा निर्धारित समयावधि तक दर की वैधता को ध्यान में रखकर प्रस्तुत करें।

(8) (B) कार्य आदेश का निरस्तीकरण :-

8-1 निर्माण कार्य का पूर्ण/अंश भाग निर्माणकर्ता द्वारा अन्य निर्माणकर्ता/निर्माणकर्ताओं को, सबलेट (Sublet) नहीं किया जावेगा। यदि यह पाया जाता है कि निर्माणकर्ता द्वारा निर्माण कार्य का पूर्ण/अंश भाग सबलेट किया गया है तो कार्य आदेश निरस्त कर दिया जावेगा।

8-2 निर्माण कार्य लोक निर्माण विभाग द्वारा निर्धारित मापदण्डों अनुसार निविदाकार द्वारा नहीं—किया जाता है। या दुग्ध संघ द्वारा दिये गये निर्देशानुसार सुधार कार्य दी गई समय—सीमा में पूर्ण नहीं किया जाता है तो कार्य आदेश निरस्त कर दिया जावेगा।

8-3 निर्माण कार्य निर्धारित अवधि में पूर्ण नहीं किया जाता है तथा निर्माण कार्य की प्रगति संतोषजनक नहीं पाई जाती है तो किसी भी समय कार्य आदेश निरस्त कर दिया जावेगा।

8-4 निविदा की शर्तों का उल्लंघन पाये जाने की स्थिति में कार्य आदेश निरस्त कर दिया जावेगा।

(9) सामान्य नियम व परिस्थितियाँ —

9-1 निविदाकार का म.प्र. लोक निर्माण विभाग में पंजीयन आवश्यक है।

9-2 पार्टनरशिप की निविदा अमान्य होगी।

9-3 निविदा में गलत पता व सही परिचय न होने के कारण निविदा स्वीकृत न हो सके तो इसका उत्तरदायित्व निविदाकर्ता का होगा दुग्ध संघ का नहीं।

9-4 निविदा खुलने के उपरांत निविदाकर्ता को निविदा वापस लेने का अधिकार नहीं होगा। निविदा में प्रेषित दरों के लिये निविदाकर्ता स्वयं जबाबदार होगा।

9-5 यदि कोई भी निविदाकर्ता इस निविदा में सम्मिलित होता है या निविदा प्रस्तुत करता है तो यह मान लिया जावेगा कि उसे निविदा की सभी शर्तें मान्य हैं। दुग्ध संघ द्वारा निविदाकर्ता की कोई भी शर्तें मान्य नहीं की जावेगी। यदि कोई नवीन अतिरिक्त कार्य कराना आवश्यक हो तो निविदाकार स्वीकृत निविदा दर पर ही कार्य करने के लिये बाध्य होगा।

9-9 सफल निविदाकर्ता को दुग्ध संघ द्वारा निर्माण कार्य आदेश जारी होने की दिनांक से 7-दिवस की समय सीमा में निविदा नियमों, शर्तों का समावेश करते हुये रु0 1000/- के, नॉन ज्यूडीशियल स्टाम्प पेपर पर अनुबंध निष्पादित करना होगा। निर्धारित समय सीमा में अनुबंध निष्पादित नहीं किये जाने पर जारी निर्माण कार्य आदेश निरस्त कर अमानत राशि राजसात कर ली जावेगी।

- 9-10 निर्माण कार्य लोक निर्माण विभाग द्वारा निर्धारित मापदण्डों अनुसार किया जावेगा । यदि निर्माण कार्य निर्धारित मापदण्डों अनुसार नहीं पाया जाता है तो कार्य आदेश निरस्त कर दिया जावेगा, तथा क्षतिपूर्ति की राशि जमा अमानत राशि / सुरक्षा निधि से वसूल की जावेगी ।
- 9-11 प्रपत्र-3 में उल्लेखित निर्माण कार्य की पूर्णतः/आंशिक रूप से कराये जाने/ लंबित रखने/ निरस्त करने का पूर्ण अधिकार मुख्य कार्यपालन अधिकारी को होगा तथा दिये गये निर्देशानुसार कम या ज्यादा कार्य करने हेतु निर्माणकर्ता बाध्य होंगे । उल्लेखित कार्य अधिक /अन्य कार्य कराये जाने पर दरें निविदा में स्वीकृत दर अनुसार होगी । एस0ओ0आर0 में वर्णित अनुसार अन्य आईटम का कार्य कराये जाने की स्थिति में स्वीकृत दर अनुसार भुगतान किया जावेगा ।
- 9-12 आवश्यकता होने पर दुग्ध संघ द्वारा नियुक्त तकनीकी सलाहकार द्वारा कार्य हेतु डिज़ाइन दी जायेगी एवं कार्यों का निरीक्षण किया जायेगा । अन्य जानकारी बाद में दी जायेगी ।
- 9-13 निर्माणकर्ता द्वारा प्रस्तुत चलित देयकों/अंतिम देयकों से नियमानुसार आयकर, सुरक्षा निधि आदिका कटौतानियमानुसार किया जावेगा, अन्य कर यथा वाणिज्य कर, रायल्टी, आदि जो शासन आदि को देय होंगे निविदाकार द्वारा स्वयं जमा किये जावेंगे । इस हेतु दुग्ध संघ जबाबदार नहीं होगा ।
- 9-14 मुख्य कार्यपालन अधिकारी भोपाल दुग्ध संघ द्वारा यदि किसी भी समय कार्य आदेश निरस्त किया जाता है तो निरस्ती आदेश जारी होने की दिनांक से 7 दिवस की समय सीमा में निर्माण स्थल पर उपलब्ध निर्माण सामग्री व मशीनरी निर्माणकर्ता को हटाना अनिवार्य होगा । निर्धारित समय सीमा में निर्माण स्थल पर उपलब्ध निर्माण सामग्री व मशीनरी न हटाये जाने की स्थिति में निर्माण सामग्री व मशीनरी के नुकसान हेतु दुग्ध संघ जबाबदार नहीं होगा ।
- 9-15 मुख्य कार्यपालन अधिकारी भोपाल दुग्ध संघ द्वारा कार्य आदेश निरस्त किये जाने पर किये गये निर्माण कार्य की राशि का भुगतान नहीं किया जावेगा तथा जमा सुरक्षा निधि की राशि राजसात कर ली जावेगी ।
- 9-16 निर्माण कार्य निर्धारित अवधि में पूर्ण नहीं किया जाता हैं तो चलित देयकों से 10 प्रतिशत की राशि **Liquidated Damage** के रूप में कटौती की जावेगी तथा कार्य पूर्णता पर अंतिम देयक से **Liquidated Damage** की राशि कटौती के निर्धारण का अधिकार मुख्यकार्यपालन अधिकारी, भोपाल सहकारी दुग्ध संघ मर्यादित भोपाल का होगा तथा इस संबंध में लिया गया निर्णय निर्माणकर्ता ठेकेदार मानने हेतु बाध्य होंगे ।
- 9-17 निर्माण कार्य के दौरान श्रम नियम, लेबर इंश्योरेंस एवं अन्य वैधानिक दायित्वों के निर्वहन की जिम्मेदारी सफल निविदाकार की होगी ।

9-18 निविदाओं में उचित दर प्राप्त नहीं होने पर दर के निर्धारण हेतु न्यूनतम दर प्रस्तुतकर्ता/निविदाकर्ता को निगोशियेशन हेतु बुलाया जा सकता है। इस हेतु पृथक से तिथि/समय सूचित की जावेगी।

9-19 मुख्य कार्यपालन अधिकारी, भोपाल सहकारी दुग्ध संघ मर्यादित भोपाल को पूर्ण अधिकार है कि वे बिना कारण सूचित किये एक अथवा समस्त निविदाओं को पूर्णतः/आंशिक रूप से मान्य/अमान्य कर सकते हैं।

9-20 कार्य की आवश्यकता को देखते हुये संघ निविदाकार से आवश्यक कार्य करा सकता है। कार्य का भुगतान वास्तविक किये गये कार्य की नाप से होगा कार्य की मात्रा में या तरीके में परिवर्तन हो सकता है। जिसका भुगतान निविदा की स्वीकृत दर पर निविदाकार को किया जाएगा।

9-21 निविदाकार को निम्न प्रमाण पत्र निविदा के साथ ऑन लाईन जमा करना वांछित दस्तावेज है। अन्यथा उसकी निविदा निरस्त हो सकती है।

(i) GST Registration.

(ii) PWD Registration.

(iii) EPF पंजीयन

(iv) ESIC पंजीयन

(v) पिछले तीन साल की ऑडिट बेलेंस शीट एवं विगत तीन वर्षों के ITR (21-22, 22-23, 23-24) संलग्न करें।

(vi) पिछले पाँच सालों में कम से कम कुल रु. 50.00 लाख के कार्य के प्रमाण पत्र जिसमें कार्यादेश एवं कार्य कम्प्लीशन प्रमाण पत्र आवश्यक है।

(vii) ज्वार्ट वेंचर मान्य नहीं होगा।

9-22 कार्य के दौरान ठेकेदार श्रमिक को किसी प्रकार की हानि जैसे- चोट लगना या दुर्घटना की स्थिति में दायित्व ठेकेदार का रहेगा। सफल निविदाकार को सामूहिक श्रमिक दुर्घटना बीमा कराना होगा। ठेकेदार को निर्धारित समय सीमा में कार्य संपादित करना होगा तथा संघ द्वारा प्रदत्त कार्य की डिजाईन के अनुसार ही संपादित करना होगा। निर्माण कार्य में सभी उपयोग की जाने वाली सामग्री ठेकेदार को स्वयं लगाना होगा। व्यवस्था किया जाना जैसे:- रेत, गिट्टी सीमेंट, लोहा, जल, बिजली टूल्स आदि।

9-23 कार्य का स्तर उत्तम होना अपेक्षित है। यद्यपि कार्य का शेडयूल आफ आइटम्स पृष्ठ क्रं0 12 से 27 पर दिया गया है। लेकिन कार्य का बिल ठेकेदार द्वारा किये गये वास्तविक कार्य के माप के अनुसार ही भुगतान किया जायेगा। कार्य की निविदा दरें भरने से पूर्व अनुसूची तृतीय का बिन्दु क्रं0 10 एवं 9-21 का अध्ययन अच्छे से किया जाना निर्देशित है।

9-24 यदि कार्य एस.ओ.आर में सम्मिलित नहीं है तो मार्केट दरों का निरीक्षण कर उनके अनुसार कार्य निविदाकार से सम्पादित कराये जायेंगे।

9-25) निविदाकार निविदा दर भरने से पूर्व स्थल का निरीक्षण कर सकते हैं। निविदा दर प्रस्तुत करने पर यह माना जायेगा कि उन्होंने कार्य स्थल का निरीक्षण भली भाँति करके निविदा दर भरी है। सशर्त निविदा मान्य नहीं की जायेगी।

9-26 कृपया ई-निविदा दर देने के पूर्व कंडिका क्रं. 9.26 के बाद का अवलोकन करें।

9-27)निर्माण कार्य पूर्णता प्रमाण पत्र आवंटित निर्माण कार्यो के संतोषजनक पूर्ण होने पर भोपाल सहकारी दुग्ध संघ द्वारा विभागीय इंजीनियर की अनुशंसा पर जारी किया जावेगा।

9-28 निविदाकार द्वारा प्रस्तुत सशर्त निविदा अमान्य मानी जावेगी।

9-29 उक्त निविदा के कार्य एवं स्वीकृत दरें अन्य स्थान, जिले एवं शहर के लिये मान्य होंगे। जो कि निविदाकार को मान्य होंगे।

(10) निविदा के दर भरने के पूर्व अति महत्वपूर्ण सूचना –

10-1 प्रायः यह देखा गया है, कि ठेकेदार अपनी निविदा उचित दर से भी न्यूनतम दर पर भरते हैं। यह प्रतियोगिता की दृष्टि से बाध्य हो कर किया जाता है। जिससे कार्य का स्तर उत्तम नहीं रह पाता है।

अतः उक्त बिन्दुओं को देखते हुये ठेकेदार बिना किसी दवाब के एवं होशोहवास में उक्त निविदा कार्य हेतु अपनी निविदा दरें ऑन लाईन प्रोफार्मा पर सन् 2024 से जारी एम.पी.पी.डबल्यू.डी., के एस.ओ.आर. की दरों से ऊपर / नीचे प्रतिशत भरें। जिससे उन्हें बाद में कार्य करने में कोई कठिनाई न हो।

(11) विवादास्पद स्थिति में अंतिम निर्णय –

11-1 यदि निविदाकर्ता/निर्माणकर्ता या दुग्ध संघ के बीच कोई विवाद होता है तो वाद आर्बीट्रेशन हेतु,एम.पी.सी.डी.एफ.,केप्रबंध संचालक को संदर्भित किया जावेगा एवं उनके द्वारा दिया गया निर्णय दोनों पक्षों को मान्य एवं बंधनकारी होगा। आर्बीट्रेशन की कार्यवाही आर्बीट्रेशन एण्ड कॉन्सिलेशन अधिनियम 1996 के अंतर्गत संदर्भित होगी।

11-2 सभी प्रकार के विवादों हेतु न्यायालयीन क्षेत्राधिकार “भोपाल” होगा।

मुख्य कार्यपालन अधिकारी
भोपाल सहकारी दुग्ध संघ मर्यादित,भोपाल।

निविदा दर प्रस्ताव पत्रक

प्रति,

मुख्य कार्यपालन अधिकारी
भोपाल सहकारी दुग्ध संघ मर्यादित.,
भोपाल।

महोदय,

आपके द्वारा जारी ई-निविदा (द्वितीय सूचना) क्रं...../भो.स.दु.सं.
/या0-सिविल/...../2025 दिनांक..... के संदर्भ में निर्माण कार्य हेतु मैं/हम अपनी दर
निम्नानुसार प्रेषित करते हैं। मैंने/हमने आपके द्वारा प्रेषित नियम व शर्तें भली भांती पढ़ व समझली है तथा
मुझे/हमे मान्य है एवं इसके परिपालन हेतु हम बाध्य है।

कार्य का विवरण	अनुमानित लागत रु. लाख में	धरोहर राशि का विवरण (ऑन लाईन से जमा करना है।)	निविदा हेतु भरी जाने वाली दर
2	3	4	5
संघ की पुताई, वॉटर प्रूफिंग का कार्य, पेवर बलॉक लगाने का कार्य, नवीन जेंट्स एवं लेडीज टॉयलेट निर्माण का कार्य, प्रशासन भवन एवं मार्केटिंग भवन के टॉयलेट रिनोवेशन का कार्य एवं कैंटीन रिनोवेशन के कार्यों के संपादन हेतु। जिस हेतु पृष्ठ क्रं0 12 से 27 पर दिये गये शेड्यूल आफ आईटम्स के विवरण के अनुसार। कृपया निविदादर ऑन लाईन पर भरने के पूर्व अनुसूची तृतीय के बिन्दु क्रं0 10 एवं 9-21 का अध्ययन भलीभांती किया जाना अपेक्षित है।	रु. 68.10 लाख	रु. 1,36,200 /—	M.P.P.W.D S.O.R प्रभावी दिनांक —01.01.2024 के अनुसार% शब्दों में.....) कम/अधिक/समान (जो लागू न हो उसे काट दें)

नोट :- निविदाकार को अपनी निविदा दरें ऑन लाईन पर दिये गये प्रोफार्मा में भरनी है।

निविदाकार के सील सहित हस्ताक्षर

नाम—

पता/ मो.नं—.....

.....

.....

(12)

Painting work Administration Sec., Marketing Sec., Audit Sec. Garrage , Boiler , Dairy Colony, Store ,New Butter Churn And All Plant Area				
S. NO.	SOR	PARTICULARS OF ITEAMS	QTY	UNIT
1	14.30	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand	9500	sqm
2	14.1	Repairs to plaster of thickness 12mm to 20mm in patches of area 2.5 sq. metres and under including cutting the patch in proper shape, raking out joints	800	sqm
3	13.41	Providing and applying white cement based putty of average thickness 1 mm, of approved brand over the plastered wall surface to prepare	1200	sqm
4	13.54.3	Finishing walls by any mechanical or manual means with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications :	18671.80	sqm
		Painting with synthetic enamel paint, having VOC (Volatile Organic Compound) content less than 150 grams/ litre,		
5	13.66.2	Two coats	600	sqm
		Providing and laying below ground unplasticised PVC pipe to with stand working pressure of 4 kg/cm2 soild		
6	19.4.1	110 m.m. Diameter OD (Min. wall thickness 3.2 m.m.)	160	rmt
		Providing and fixing unplasticised PVC moulded fittings/ accessories for unplasticised Rigid PVC soil and waste		
7	17.59.5.2	110 mm bend	25	each
	17.59.4.2	110 mm tee	20	each
		Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc.		
8	21.3.1	With float glass panes of 4.0 mm thickness (weight not less than 10 kg/sqm	60	sqm

Near Time Office Construction of Gents and Ladies Toilet				
S. NO.	S.O.R.	PARTICULARS OF ITEAMS	QTY	UNIT
1	2.6	Earth work in excavation by mechanical means (Hydraulic excavator) / manual	35.280	cum
2	5.9.1	Foundations, footings, bases of columns, etc. for concrete upto plinth leve	79.98	sqm
3	4.1.1.4	Providing and laying in position cement concrete of specified grade excluding the		
		M-10Nominal (Mix-1 Cement : 3 sand : 6 graded stone aggregate	1.648	cum
4	5.16.6	Thermo-Mechanically Treated bars. (TMT/TMX) FE 500 or more conforming to IS 1786	960.00	kg
5	5.1	Providing and laying in position specified grade of reinforced cement		
		M-20 Grade Concrete	12.064	cum
6	2.24	Filling available excavated earth (excluding hard rock/Ordinary rock) in trenches, plinth,	35.280	cum
7	2.26	Supplying and filling in plinth with crusher stone dust / coarse sand under floors including, watering,	6.00	cum
8	6.4.2	Brick work with well burnt /cm2 chimney chimney bricks in bulls pattern bricks in trench kiln, crushing strength	13.93	cum
9	13.3.2	20 mm cement plaster of mix		
		1:6 (1 cement : 6 sand)	96.46	cum
10	11.5	Providing and fixing Ceramic glazed wall tiles 300x450 mm or more (having thickness 6 to 7 mm) of 1st quality	45.20	sqm
11	11.76.1	Providing and laying vitrified floor tiles (without soluble salt) or printed (with soluble salt) Nano polished		
		Plain ivory light shade Size 600X600mm thickness 9-10mm	19.50	sqm

		(14)		
12	13.54.3	Finishing walls by any mechanical or manual means with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications :	224.38	sqm
13	11.29.2.3	Granite work gang saw cut (polished and machine cut) of thickness 18mm for wall lining (veneer work)		
		Gray/Pink/Brown or equivalent with various patterns	6.48	sqm
14	10.22.2	Steel work welded in built up sections/ framed work including cutting, hoisting,	195	k.g.
15		CPVC pipes internal work Providing and fixing Chlorinated Polyvinyl Chloride (CPVC		
	18.6.1.1	15 mm nominal outer dia .Pipes.	18	M
	18.6.1.2	20 mm nominal outer dia .Pipes.	12	M
	18.10.1.1	For 15.88 mm outer diaPipe elbow	28	No.
16	17.71.1	Providing and fixing CP brass waste coupling of approved quality and make for sink and wash basin.	2	No.
17	18.35	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:893115 mm nominal bor	3	No.
18	18.31	Providing and fixing C.P. brass bib cock of approved quality conforming to IS: 8931and weighing not less than 400gm, 15 mm nominal	3	No.
19	18.17.2.1	Providing and fixing Unplasticised P.V.C. connection pipe with PTMT Nuts collar and bush of approved quality and co		
		45 cm length.	7	No.
20	17.11.2	White Vitreous China Wash basin size 630x450 mm with a single 15 mm C.P. brass pillar tap.	2	No.
21	18.47.1	Providing and fixing PTMT, push cock of approved quality and colour.		
		15 mm nominal bore, 98mm long. Weighing not less than 75 gms.	5	No.
22	19.4	Providing and laying below ground unplasticised PVC pipe to with stand working pressure of 4 kg/cm2 soil waste pipes		

		(15)		
	19.4.2	160 mm diameter OD (min. wall thickness 4.0mm)	12	M
	19.4.1	110 mm diameter OD (min. wall thickness 3.2mm)	10	M
23		Providing and fixing unplasticised PVC moulded fittings/ accessories for unplasticised Rigid PVC soil and waste pipes		
		Coupler		
		110 mm	6	No.
		Bend		
		110 mm	8	No.
		Tee		
		110 mm	6	No.
24	17.64.2.2	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete.		
		40 mm dia	5	No.
		Constructing masonry Chamber 60x45x50 cm inside, in brick work in cement mortar 1:4 (1 cement : 4 sand)		
25	18.21.1	With common burnt clay bricks of 25 kg /sqcm compressive strength	2	No.
26	17.27	Providing and fixing white vitreous china flat back half stall urinal of size 580x380x350mm.	3	No.
27	18.28	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover	1000.00	Lit
		Providing and fixing brass stop cock of approved quality :		
28	18.30.1	15 mm nominal bore	5	No.
		Providing and fixing PTMT Ball cock of approved quality, c		
29	18.51.2	20 mm nominal bore, 120 mm long. Weighing not less than 198 gms.	2	No.
		Providing and fixing PTMT extension nipple for water tank		
30	18.53.2	20mm nominal bore. Weighing not less than 40gms.	2	No.
		Electrical work		
29	5.1	Point wiring (excluding metallic switch box & sheet but including switches, sockets, lamp holders/ceiling roses etc)		
		Light Point/ Fan Points.		
	5.1.1	Short point	1	Each

		(16)		
	5.1.1.2	Medium point	2	Each
30		3 Pin 6 Amp socket outlet on Sepatate Board		
	5.1.3.1	Short point	1	Each
	5.1.3.2	Medium point	2	Each
31	18.2	Supplying and fixing of approved make modular type G.I. metal box 1.2mm minimum thick and depth 50mm		
	18.2.4	6 Module metal box	3	Each
	18.2.6	12 Module metal box	2	Each
32		Supplying and drawing single core PVC insulated cable FRLS with copper multi		
	19.1.1.1	1.5 sq. mm. wire		
	19.1.1.1	2 X 1.5 sq. mm.	65	Mtr
	19.1.1.1	3 X 1.5 sq. mm.	85	Mtr
		Supply & fixing of I.S.I. marked porcelain rewireable fuse unit of approved make or conforming to I.S. 2086-1982		
33	25.16.2	16Amp/415 Volts or 32Amp/240 Volts	4	Each
34	30.5.2	Supplying and fixing of deluxe fresh air fan with louvers (ventilating fan) with self closing louvers of decorative PVC	3	Each
35	31.3.2	Supply and fixing Led tube rod comprising of LED tube with non-integral/integral driver, upto 6500K	6	Each
		SupplyandfixingrecessedmountingLEDdownlighter,LEDof 1to 3Watt each assemble donsinge MCPCB, having color temp. upto 6500		
36	31.6.4	12 Watt, color temp 3000-6500k as required	6	Each

(17)

Water Proofing Work at Plant , Lab , Processing Hall , Administration Building, Marketing Building , Security Cabin and Dairy Colony				
		Dismantling tile/ Kota stone/ Marble / Granite work in floors/walls and roofs laid in cement mortar including stacking material within 50 metres lead.		
1	15.11.1	For thickness of tiles 10 mm to 25 mm.	2435.32	Sqm
2	22.7	Providing and laying integral cement based water proofing treatment including preparation of surface as required for treatment of roofs,	800.00	Sqm
3	22.6	Providing and laying water proofing treatment on roofs of slabs by applying cement slurry mixed with water proofing cement compound consisting of applying	2586.61	Sqm
Paver Block Fixing at New Butter Churn Front Area				
1	2.6	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in	40.80	Cum
2	4.1.1.4	Providing and laying in position cement concrete of specified grade excluding the cost	37.80	Cum
3	2.26	Supplying and filling in plinth with crusher stone dust / coarse sand under floors including, watering, ramming and compacting in layers not exceedin	25.20	Cum
4	11.66	Providing and laying factory made machine pressed precast cement concrete interlocking paver block of any shape and size conforming to IS:15658	204.00	Cum

RCC Currtain Wall

1	5.9.1	Foundations, footings, bases of columns, etc. for concrete upto plinth leve	101.05	Sqm
2	5.16.6	Thermo-Mechanically Treated bars. (TMT/TMX) FE 500 or more conforming to IS 1786	650.00	kg
3	5.1	Providing and laying in position specified grade of reinforced cement concrete (with 20mm nominal size graded stone		
		M-20 Grade Concrete	11.280	cum

TOILET RENOVATION WORK MARKETING BUILDING

1	4.1.1.4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work upto plinth level :		
		M-10Nominal (Mix-1 Cement : 3 sand : 6 graded stone aggregate	5.00	cum
2	11.5	Providing and fixing Ceramic glazed wall tiles 300x450 mm or more (having thickness 6 to 7 mm) of 1st quality	180.00	sqm
		Providing and laying vitrified floor tiles (without soluble salt) or printed (with soluble salt) Nano polished		
3	11.76.1	Plain ivory light shade Size 600X600mm thickness 9-10mm	60.00	sqm
4	13.54.3	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @0.90 ltr/10 sqm	224.38	sqm
5	11.29.2.3	Granite work gang saw cut (polished and machine cut) of thickness 18mm for wall lining (veneer work), backing filled		
			4.86	sqm
6	10.22.2	Steel work welded in built up sections/ framed work including cutting, hoisting,	180	k.g.
7		CPVC pipes internal work Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes,		
	18.6.1.1	15 mm nominal outer dia .Pipes.	48	M
	18.7.2	20 mm nominal outer dia .Pipes.	36	M
	18.10.1.1	For 15.88 mm outer diaPipe elbow	40	No.
8	17.71.1	Providing and fixing CP brass waste coupling of approved quality and make for sink and wash basin.	10	No.
9	18.31	Providing and fixing C.P. brass bib cock of approved quality conforming to IS: 8931and weighing not less than 400gm, 15 mm nominal	10	No.
10	18.17.2.1	Providing and fixing Unplasticised P.V.C. connection pipe with PTMT Nuts collar and bush of approved quality and co		
		45 cm length.	15	No.
11	17.11.2	White Vitreous China Wash basin size 630x450 mm with a single 15 mm C.P. brass pillar tap.	8	No.

		(19)		
12	18.47.1	Providing and fixing PTMT, push cock of approved quality and colour.		
		15 mm nominal bore, 98mm long. Weighing not less than 75 gms.	8	No.
13	19.4	Providing and laying below ground unplasticised PVC pipe to with stand working pressure of 4 kg/cm ² soil waste pipes		
	19.4.2	160 mm diameter OD (min. wall thickness 4.0mm)	40	M
	19.4.1	110 mm diameter OD (min. wall thickness 3.2mm)	55	M
14		Providing and fixing unplasticised PVC moulded fittings/ accessories for unplasticised Rigid PVC soil and waste pipes		
		Coupler		
		110 mm	10	No.
		Bend		
		110 mm	12	No.
		Tee		
		110 mm	8	No.
15	17.64.1.2	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete.		
		40 mm dia	15	No.
		Constructing masonry Chamber 60x45x50 cm inside, in brick work in cement mortar 1:4 (1 cement : 4 sand)		
16	18.21.1	With common burnt clay bricks of 25 kg /sqcm compressive strength	4	No.
17	17.27	Providing and fixing white vitreous china flat back half stall urinal of size 580x380x350mm.	3	No.
18	18.28	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and	1500.00	Lit
		Electrical work		
19	5.1	Point wiring (excluding metallic switch box & sheet but including switches, sockets, lamp holders/ceiling roses etc)		
		Light Point/ Fan Points.		
	5.1.1	Short point	3	Each
	5.1.1.2	Medium point	2	Each
20		3 Pin 6 Amp socket outlet on Sepatate Board		
	5.1.3.1	Short point	3	Each
	5.1.3.2	Medium point	2	Each

		(20)		
21	18.2	Supplying and fixing of approved make modular type G.I. metal box 1.2mm minimum thick and depth 50mm for		
	18.2.4	6 Module metal box	3	Each
	18.2.6	12 Module metal box	2	Each
22		Supplying and drawing single core PVC insulated cable FRLS with copper multi strand conductor ISI marked in existing rigid PVC casing and capping/conduit in surface or concealed as per specification.		
	19.1.1.1	1.5 sq. mm. wire		
	19.1.1.1	2 X 1.5 sq. mm.	115	Mtr
	19.1.1.1	3 X 1.5 sq. mm.	168	Mtr
		Supply & fixing of I.S.I. marked porcelain rewirable fuse unit of approved make or conforming to I.S. 2086-1982		
23	25.16.2	16Amp/415 Volts or 32Amp/240 Volts	4	Each
24	30.5.2	Supplying and fixing of deluxe fresh air fan with louvers (ventilating fan) with self closing louvers of decorative	3	Each
25	31.3.2	Supply and fixing Led tube rod comprising of LED tube with non-integral/integral driver, upto 6500K color temp having 40000 burning hrs life	9	Each
26	15.2.1	Demolishing cement concrete manually/by mechanical means including disposal of material within 50 metres	15.00	cum
27	15.11.1	Dismantling tile/ Kota stone/ Marble / Granite work in floors/walls and roofs laid	210.00	Sqm
		Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10		
28	17.2.1	W.C. pan with ISI marked white solid plastic seat and lid	6	Each

(21)

Miscellaneous work

		Canteen work		
1	15.2.1	Demolishing cement concrete manually/by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-in- Charge.	2	cum
2	15.6.3	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal	2	cum
3	6.4.2	Brick work with well burnt /cm2 chimney chimney bricks in bulls pattern bricks in trench kiln, crushing strength	6.05	cum
4	13.3.2	20 mm cement plaster of mix		
		1:6 (1 cement : 6 sand)	50.80	cum
5	10.22.2	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing	22	k.g.
6	11.29.2.3	Granite work gang saw cut (polished and machine cut) of thickness 18mm for wall lining (veneer work), backing		
		Gray/Pink/Brown or equivalent with various patterns	4.86	sqm
		PLANT WORK		
7	11.36	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed	90.00	sqm
		Stone work (machine cut edges) for wall lining etc. (veneer work) up to 10 meter height backing filled with a grout of 12mm thick cement mortar 1:3 (		
8	7.21.1.5	30 mm thick.	100.00	sqm
9	2.26	Supplying and filling in plinth with crusher stone dust / coarse sand under floors including, watering, ramming and compacting in layers not exceedin	15.26	Cum
10	11.66	Providing and laying factory made machine pressed precast cement concrete interlocking paver block of any	90.00	Cum

TOILET RENOVATION WORK ADMINISTRATION BUILDING

1	15.11.1	Dismantling tile/ Kota stone/ Marble / Granite work in floors/walls and roofs laid	160.40	Sqm
2	4.1.1.4	Providing and laying in position cement concrete of specified grade excluding the cost		
		M-10Nominal (Mix-1 Cement : 3 sand : 6 graded stone aggregate	2.50	cum
	11.82.1.5	Providing and laying digital print random design(PGVT)/(GVT) vitrified tiles in different sizes with water absorption less than 0.05% and conforming	140.40	Sqm
	11.82.1.1	Size 600X600 mm thickness 9-10 mm	36.00	Sqm
3	13.54.3	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied	83.00	sqm
4	11.29.2.3	Granite work gang saw cut (polished and machine cut) of thickness 18mm for wall lining (veneer work),		
		Gray/Pink/Brown or equivalent with various patterns	10.86	sqm
		Providing and fixing ISI marked flush door shutters conforming to IS: 2202 (Part I) decorative type, core of		
5	9.18.2	30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws.	6	Sqm
6	9.95	Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo	3	each
		Providing and fixing ISI marked stainless steel door latches with screws etc. complete :		
7	9.68.1	300x20x6 mm	3	each
		Providing and fixing ISI marked stainless steel handles with necessary screws etc. complete :		
8	9.69.1	125 mm	6	each
		Providing and fixing ISI marked stainless steel sliding door bolts with nuts and screws etc. complete:		
9	9.65.1	300x16 mm	3	each

		(23)		
		CPVC pipes internal work Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes,		
10	18.6.1.1	15 mm nominal outer dia .Pipes.	52	M
11	18.6.1.2	20 mm nominal outer dia .Pipes.	22	M
12	18.10.1.1	For 15.88 mm outer diaPipe elbow	20	No.
13	17.71.1	Providing and fixing CP brass waste coupling of approved quality and make for sink and wash basin.	3	No.
14	18.31	Providing and fixing C.P. brass bib cock of approved quality conforming to IS: 8931and weighing not less than 400gm, 15 mm nominal	6	No.
15	18.35	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality	6	No.
15	18.17.2.2	Providing and fixing Unplasticised P.V.C. connection pipe with PTMT Nuts collar and bush of approved quality and co		
		45 cm length.	15	No.
16	17.11.1	White Vitreous China Wash basin size 630x450 mm with a single 15 mm C.P. brass pillar tap. Back Pair	3	No.
17	18.47.1	Providing and fixing PTMT, push cock of approved quality and colour.		
		15 mm nominal bore, 98mm long. Weighing not less than 75 gms.	6	No.
18	19.4	Providing and laying below ground unplasticised PVC pipe to with stand working pressure of 4 kg/cm2 soild waste pipes		
	19.4.2	160 mm diameter OD (min. wall thickness 4.0mm)	20	M
	19.4.1	110 mm diameter OD (min. wall thickness 3.2mm)	30	M
19		Providing and fixing unplasticised PVC moulded fittings/ accessories for unplasticised Rigid PVC soil and waste pipes		
		Coupler		
		110 mm	12	No.
		Bend		
		110 mm	10	No.
		Tee		
		110 mm	8	No.

		(24)		
20	17.64.1.2	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete.		
		40 mm dia	10	No.
		Constructing masonry Chamber 60x45x50 cm inside, in brick work in cement mortar 1:4 (1 cement : 4 sand)		
21	18.21.1	With common burnt clay bricks of 25 kg /sqcm compressive strength	5	No.
22	17.27	Providing and fixing white vitreous china flat back half stall urinal of size 580x380x350mm.	6	No.
23	18.28	Providing and placing on terrace (at all floor levels) polyethylene water storage tank ISI : 12701 marked with cover and suitable	1000.00	Lit
		Providing and fixing PTMT Ball cock of approved quality, c		
29	18.51.2	20 mm nominal bore, 120 mm long. Weighing not less than 198 gms.	2	No.
		Providing and fixing PTMT extension nipple for water tank		
30	18.53.2	20mm nominal bore. Weighing not less than 40gms.	2	No.
		Electrical work		
24	5.1	Point wiring (excluding metallic switch box & sheet but including switches, sockets, lamp holders/ceiling roses etc)		
		Light Point/ Fan Points.		
	5.1.1	Short point	6	Each
	5.1.1.2	Medium point	2	Each
25		3 Pin 6 Amp socket outlet on Sepatate Board		
	5.1.3.1	Short point	3	Each
	5.1.3.2	Medium point	2	Each
26	18.2	Supplying and fixing of approved make modular type G.I. metal box 1.2mm minimum thick and depth 50m		
	18.2.4	6 Module metal box	6	Each
	18.2.6	12 Module metal box	2	Each
27		Supplying and drawing single core PVC insulated cable FRLS with copper multi strand		
	19.1.1.1	1.5 sq. mm. wire		
	19.1.1.1	2 X 1.5 sq. mm.	52	Mtr
	19.1.1.1	3 X 1.5 sq. mm.	68	Mtr

		(25)		
		Supply & fixing of I.S.I. marked porcelain rewireable fuse unit of approved make or conforming to I.S. 2086-1982		
28	25.16.2	16Amp/415 Volts or 32Amp/240 Volts	4	Each
29	30.5.2	Supplying and fixing of deluxe fresh air fan with louvers (ventilating fan) with self closing louvers of decorative PVC	4	Each
30	31.3.2	Supply and fixing Led tube rod comprising of LED tube with non-integral/integral driver, upto 6500K color temp having 40000 burning hrs life	9	Each
31	25.85	Providing and fixing Flash touch-free infrared hand dryer with 1150W rated power & carbon brush motor Material: 304 Stainless Steel Finish: Stainless Steel Finish (Premium Range)	3	Each
31	15.2.1	Demolishing cement concrete manually/by mechanical means including disposal of material within 50 metres lead as per direction of Engineer-inCharge Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	15.00	cum
32	21.22	Providing and fixing 12 mm thick toughened glass including all connectors	8.80	sqm
33	21.18	Providing and fixing 12 mm thick frameless toughened glass door shutter of approved brand and manufacture,	6.30	sqm
33	17.2.1	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre	3	Each
34	25.5	Providing and fixing in position best Indian Stainless steel made (0.3 micron Chrome and 10 micron Nickel plated)	3	Each
35	25.53	Providing and fixing in position best Indian C. P. Brass made (0.3 micron Chrome and 10 micron Nickel plated) Soap Dish Holder. (Premium Range)	3	Each

		(26)		
35	18.34	Providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make	3	Each
		Supply and fixing recessed mounting LED down lighter, LED of 1to 3Watt each assemble donsngle MCPCB, having color tempup to 6500K		
36	31.6.4	12 Watt, color temp 3000-6500k as required	6	Each
		Total Amount		5771084
		in Net Total Addition of 18% GST		1038795
		payable Amount		6809879

Say Rs. 68.10 Lakhs (Including 18% G.S.T.)

(27)

Sr. No.	Items.	Make
1.	Electrical Wire	Havells, Finolex, V-Guard
2.	Light (Luminous)	Havells, Syska, Crompton's, Wipro,
3.	Wash Basin	Jaguar, Hindware, Cera, Parryware
4.	Tap	Jaguar, Cera, Hindware
5.	PVC Pipe	Ashirvad, Astral, Supreme
6.	CPVC Pipe	Astral, Ashirvad, Supreme
7.	Tiles	Kajaria, Somaniya, Johnson
8.	Sand	Narmada Sand
9.	Cement	Ultra Tech, ACC, JK Cement, Ambuja cement
10.	Paint	Asian, Burger Birla Opus
11.	Steel	Tata, Jindal, Sail

कार्यालय प्रमुख अभियंता,
म.प्र. लोक निर्माण विभाग, निर्माण भवन, भोपाल (म.प्र.)

website : www.mp.gov.in/pwdmp

email : pwdbhop@mp.nic.in

phone - 0755-2551485, fax - 2556527

क्रमांक 401/एम.डी.आर./निविदा /2017-18/1298
प्रति,

भोपाल, दिनांक 09/08/17

समस्त कार्यपालन यंत्री
लोक निर्माण विभाग संभाग

विषय:- लोक निर्माण विभाग द्वारा भविष्य में बुलाये जाने वाली निविदाओं के लिए माल एवं सेवाकर (जी0एस0टी0) के संबंध में बाबत।

संदर्भ :- मध्य प्रदेश शासन, लोक निर्माण विभाग, मंत्रालय के आदेश क्रमांक एफ/58/15/17/19/यो भोपाल, दिनांक 05 अगस्त 2017

—00—

विषयांतर्गत संबंध में शासन के संदर्भित आदेश की छायाप्रति संलग्न कर लेख है कि विभाग अंतर्गत भविष्य में बुलाई जाने वाली निविदाओं के लिए जी0एस0टी0 हेतु निविदा प्रपत्र में निम्नानुसार समावेश करना सुनिश्चित करें।

SECTION 3 (Conditions of Contract)
Part - II Special Conditions of Contract [SCC]
Additional Special Conditions of Contract

BIDDERS ARE REQUIRED TO OFFER THEIR BIDS EXCLUSIVE OF APPLICABLE GST. THE GST SHALL BE PAID BY THE GOVT. TO THE CONTRACTOR SEPARATELY. THE GOVT. ORDER IN THIS REGARD IS BEING UPLOADED HERE WITH साथ ही निविदा प्रपत्र में संदर्भित आदेश की छायाप्रति संलग्न की जावे।
संलग्न :- उपरोक्तानुसार।


मुख्य अभियंता (प्रमुख) (म.प्र.)
कार्या. प्रमुख अभियंता, लोक निर्माण विभाग
भोपाल (म.प्र.)

क्रमांक 401/एम.डी.आर./निविदा /2017-18/1299

भोपाल, दिनांक 09/08/17

प्रतिलिपि :- (1) समस्त मुख्य अभियंता लोक निर्माण विभाग।

(2) समस्त अधीक्षण यंत्री लोक निर्माण विभाग।

सूचनार्थ एवं आवश्यक कार्यवाही हेतु प्रस्तुत।


मुख्य अभियंता (प्रमुख) (म.प्र.)
कार्या. प्रमुख अभियंता, लोक निर्माण विभाग
भोपाल (म.प्र.)